

LEGEND

- LIGHT DUTY PAVEMENT
- HEAVY DUTY PAVEMENT (EXCLUDING IDOT R.O.W.)
- PAVEMENT TO REMAIN
- CONCRETE PAVEMENT OR APRON
- CONCRETE SIDEWALK
- CONCRETE SIDEWALK HC RAMP (5' WIDE UNLESS NOTED)
- REVERSE PITCH CURB
- DEPRESSED CURB & GUTTER
- DETECTABLE WARNING SURFACE

NOTES:

1. ALL DIMENSIONS ARE TO THE BACK OF CURB UNLESS OTHERWISE NOTED.
2. ALL CURBS AND GUTTERS ARE REVERSED PITCH UNLESS OTHERWISE NOTED.
3. SEE DETAIL SHEETS FOR PAVEMENT SECTION DETAILS.
4. ALL PAVEMENT MARKINGS SHALL BE PAINT.
5. ALL ACCESSIBLE PARKING SPACE SIGNAGE SHALL CONFORM TO ILLINOIS ACCESSIBILITY CODE.
6. SEE ARCHITECTURAL DRAWINGS FOR DESIGN AND DETAILS OF THE BUILDINGS
7. PARKING STALLS TO THE WEST OF THE EXISTING NAPA BUILDING (SOUTH OF THE SITE) NEED TO BE REMOVED PRIOR TO THE CROSS-CONNECTION BEING INSTALLED.
8. WHERE NEW CONCRETE CURB AND GUTTER OR SIDEWALK CONNECTS TO EXISTING, DOWEL BARS AND EXPANSION JOINT FILLER MATERIAL ARE NEEDED.

SIGN LEGEND:

- R1-1
30" x 30"
- R3-5R
30" x 36"
- R250 FINE
36" x 36"
R7-8
- R3-2
36" x 36"
- R5-1
30" x 30"

NOTE: ② INDICATES SIGN ① MOUNTED ABOVE SIGN ①


NO.	DATE	REMARKS

NO.	DATE	REMARKS

SITE PLAN
CULVERS OF GLENVIEW
GLENVIEW, ILLINOIS

CONSULTING ENGINEERS
SITE DEVELOPMENT ENGINEERS
LAND SURVEYORS

9575 W. Higgins Road, Suite 700,
Rosemont, Illinois 60018
Phone: (847) 676-4060 Fax: (847) 676-4065



SPACECO INC.
FILENAME:
9137.02_SITE_PLA1.dgn
DATE:
6/21/17
JOB NO.
9137.02

SHEET
SITE
1 OF 1